



**Scope of Work:**

Replace Steam Heat System Building 110

This project consisted of labor, materials, equipment, facilities supervision, testing and all related costs to replace heating system for building 110. Removal & disposal of heating system pipes & fittings wrapped with asbestos containing insulation. Starting at the main steam and condensate lines, removal & disposal of all piping, fittings, insulation, and unit & fin tube heaters, and their associated controls. Install new heating system components include piping, fittings, insulation, controls, and unit & fin tube heaters. Provide operation and maintenance personnel on the new heating system. Provide as-built drawings

**Location:**

1 Buffington Street Watervliet, NY 12189-4000

**Contract Amount:**

\$1,144,399.00

**Completion Date:**

TBA